MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

Received for record the 12 day of MAY A. D. 1999 at 10:30 o'clock A m., and recorded in Liber 7 of CORNERS on page 136.

Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic (County)

	Located In:	Corner Code ##
1. Public Land Survey	T 46N R 43W	M-4
	T R	
	T R	
	T 46N R 42W	A-4
2. Property Controlling	S T R	
in Section	S T R	
3. Miscellaneous	S T R	
Property in Sec.	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



Quarter Corner 12 & 7; T.46 N., R.42-43 W.

Richard L. Drahn, in a field survey on April 9, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 8/6/1847. Original B.T.s --- Y. Birch 22" S.71 E. 25 links (16.50') --- Sugar 9" N.23 W. 20 links (13.20') ---

Corner restored by Richard L. Drahn, RLS 21564 on 6/30/78 at the site of a wood post and at record bearing and distance from the remains of the original B.T.s He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following:

6"	Maple	N.05 E.	12.2'
4"	Maple	S.77 E.	23.9'
8"	Maple	S.31 W.	31.1'
7'	Steel sign rail	N.85 E.	1.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County Liber 1, Page 438 on 1/17/79.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

7"	Sugar Maple	N.05 E.	12.19'
6"	Sugar Maple	S.77 E.	23.91'
8"	Sugar Maple	S.32 W.	31.01'
7'	Steel sign rail	N.87 E.	1.75'

Fragments of Yellow Birch bark are all that remains of the original B.T.s

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

4"	Sugar Maple	N.70 W.	35.20'

FIELD CROW APPROVED
Richard L. Drahn 5/11/99
COUNTY REPRESENTATIVE

STATE OF MICHIGAN
RICHARD L. DRAHN
LAND SURVEYOR
No. 21564
REGISTERED LAND SURVEYOR

Signed by Richard L. Drahn Date April 29, 1999

Surveyor's Michigan License No. 21564

USFS G-25

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983