

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Gogebic (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 46N R 42W \_\_\_\_\_ A-5 \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T 46N R 43W \_\_\_\_\_ M-5 \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_  
 Section Corner 7, 18, 12 & 13; T.46N, R.42-43W.

Register's Office }  
 Gogebic County } ss.

Received for record the  
2<sup>nd</sup> day of MARCH  
 A. D. 1995 at 9:10 o'clock  
A m., and recorded in  
 Liber 5 of CORNERS  
 on page 208  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Richard L. Drahn, in a field survey on May 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by John Burt, U.S. Deputy Surveyor, on August 6, 1847. Original bearing trees:

Cedar	16"	N.29W.	27 links	(17.82 feet)
Sugar	16"	S.74E.	13 links	( 8.58 feet)
Hemlock	12"	S.65W.	17 links	(11.22 feet)
Hemlock	10"	N.21E.	23 links	(15.18 feet)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No G.L.O. evidence remains. Re-established corner position on line between and proportionate distance from the section corner of 18, 19, 13 & 24 and the quarter corner of 7 & 12; T.46N., R.42-43W.

PEER GROUP APPROVED  
Richard L. Drahn 3/1/95  
 COUNTY REPRESENTATIVE



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position I set a 2 1/2" diameter by 30" long aluminum monument with a 3 1/4" aluminum cap with magnet stamped to read T.46N., R.42-43W.; S-7, S-18, S-12, S-13; 1994 R.L.S. 21564 from which I established the following new blazed and scribed bearing trees and/or objects:

6"	Sugar Maple	N.04E.	21.74 feet
6"	Sugar Maple	S.86E.	46.88 feet
4"	Aspen	S.33W.	7.55 feet
6'	Steel Rail	N.50E.	1.76 feet

Signed by Richard L. Drahn Date February 6, 1995  
 Surveyor's Michigan License No. 21564