LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office Gogebic County

	٠,			
ļ	Received	for rec	ærd t	he
22	day	01 MA	IR GA	
A. D. 19	95 st	9:10	_o'clo	ck.
Liber				
on nage	209			
Remai	ia Coll	ms	Jeau	ty
-	lie	gister (of Do	eda

Register of Deeds Stamp & File Number

For corners in Located In: Corner Code ## _Gogebic т <u>46N в 42</u>W 1. Public Land Survey 464. R 43W. **Property Controlling** in Section 3. Miscellaneous S Property in Sec. S

_ , Recorded Plat . 5 Private Claims 1/4 Corner 18 & 13; T.46N., R.42-43W.

, 19 ⁹⁴ May 12, I. Richard L. Drahn, in a field survey on do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Corner established by John Burt, U.S. Deputy Surveyor, on August 6, 1847. Original bearing

trees: Cedar

Cedar

S.82E.

N.45W.

25 links 39 links

10

11

12

(16.50 feet) (25.74 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: No G.L.O. evidence remains. Re-established corner position on line between and proportionate distance from, the section corner of 18, 19, 13 & 24 and the quarter corner of 7 & 12.

Description of monument for corner and accessories established to perpetuate locating the position of the corner: At the corner position I set a 3/4" x 3 foot solid aluminum marsh rod with a 3 1/4" aluminum cap with magnet, stamped to read: T.46N., R.42-43W.; 1/4; S-13, S-18; 1994; R.L.S. 21564 from which $ar{ extsf{I}}$ established the following new blazed and scribed bearing trees and/or objects:

7.75 feet N.57W. 5¹¹ Cedar ۳9 S.64E. 18.36 feet Cedar 11" 25.32 feet S.66W. Cedar 2.23 feet N.59E. Steel Rail 61

Surveyor's Michigan License No. 21564

February 6, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975

FRED

REVISED JAN., 1983

RICHARD

L. DRAHN LAND SURVEYOR No. 21564

EMAI