

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } 85.

For corners in

Gogebic
(County)

Located In: Corner Code #

1. Public Land Survey

T 46N R 43W M-8
T R

2. Property Controlling in Section

T 46N R 42W A-8
S T R

3. Miscellaneous Property in Sec.

S T R
S T R
S T R

Received for record the
12 day of MAY

A. D. 1999 at 10:30 o'clock
A m., and recorded in

Liber 7 of CORNERS

on page 138

Phyllis Collins Depierre
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 19 & 24; T.46 N., R.42-43 W.

Richard L. Drahn, in a field survey on May 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 8/6/1847. Original corner tree was a 22" Yellow Birch. No original B.T.s were referenced. 1935 acquisition survey crews recovered the corner tree still scribed and placed a location poster on the east side of the corner tree. They also placed a location poster on the west side of a 24" Sugar 7 ft. east of the corner tree.

Corner tree recovered by Richard L. Drahn, RLS 21564 on 6/30/81 with the 1935 location poster still attached. Tag on 24" Sugar N.70 E. 6.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He set a 2" X 30" aluminum reference monument 3.5' south of the center of the original corner tree and the following new B.T.s (bearings and distances from the center of the corner tree): --- 8" Sugar Maple N.33 E. 15.4' --- 10" White Spruce S.55 E. 39.8' --- 8" Sugar Maple S.38 W. 13.7' --- 7' Metal sign rail S.79 E. 5.0' ---

Corner recorded in Gogebic County Liber 2, Page 210 on 3/10/82.

The original Yellow Birch corner tree is now a 38" broken stub. The reference monument was recovered as described and the new B.T.s as follows:

11" Sugar Maple N.34 E. 15.6' (est. to center of Birch)
10" Dead White Spruce S.57 E. 40.0' " " " " " "

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10" Sugar Maple S.35 W. 14.0' " " " " " "
7' Steel sign rail S.80 E. 4.8' " " " " " "

Corner research on file with Gogebic County records.

New bearing tree referenced:

10" Red Maple S.68 E. 22.9'

PEER GROUP APPROVED

Richard L. Drahn 5/11/99

COURT APPROVED

Date May 6, 1999

Signed by Richard L. Drahn

Surveyor's Michigan License No. 21564

