

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County }

For corners in

Gogebic  
(County)

Located in:

Corner Code #

1. Public Land Survey

T 46N R 43W M-9

2. Property Controlling  
in Section

S      T      R     

3. Miscellaneous  
Property in Sec.

S      T      R       
S      T      R     

Received for record the  
21<sup>ST</sup> day of JULY  
A. D. 1999 at 1:15 o'clock  
P m., and recorded in  
Liber 7 of CORNERS  
on page 189

Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Section Corner 24, 25, 19 & 30; T.46 N., R.42-43 W.

I, Richard L. Drahn, in a field survey on June 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 8/6/1847. Original bearing trees:

- 1. Y. Birch 26" S.10°W. 55 links (36.30')
- 2. Sugar 12" N.24° E. 19 links (12.54')
- 3. Sugar 10" S.50° E. 5 links (3.30')
- 4. Sugar 7" N.74° W. 43 links (28.38')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the following original bearing tree remains:

- 1. Large series of root holes, species undetermined.
- 2. Large, deep stump hole.
- 3. Badly decayed 18"-24" Sugar Maple stump.
- 4. Deep stump hole.

The 4.50 chain distance south from corner to "top of ridge 25ft. WSW" checks.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree)

- Sugar Maple 8" N.19° E. 18.01'
- Sugar Maple 7" S.87° W. 6.39'
- Sugar Maple 11" S.12° W. 43.67'
- Steel sign rail 6' S.69° E. 2.17'

PEER GROUP APPROVED  
Richard L. Drahn 7/20/99  
COUNTY REGISTER



Signed by Richard L. Drahn Date June 20, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983