

**SURVEY &  
REMONUMENTATION**

NOV 12 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic Located In: Corner Code #  
(County)

1. Public Land Survey T46NR 43W A, 10-11 002  
T46NR 44W M 10-11 002  
T R  
T R  
T R

2. Property Controlling in Section S T R  
S T R

3. Miscellaneous Property in Sec. S T R  
S T R

Received for record the  
9<sup>TH</sup> day of OCTOBER  
A. D. 1997 at 10:50 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 216  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John P. Goss, in a field survey on Oct. 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

M.C. comm. to sec's 25 & 30

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on Aug. 8, 1847.  
Original bearing trees: Cedar 10" S 47° E 8 links  
Spruce 14" N 53° E 26 links

Richard Drahn, RLS, on May 25, 1975 restored corner position at record bearing and distance from the remains of two original bearing trees: A stump hole with Cedar roots and Large Spruce wingfall with stump decayed to ground line. He set a 2½" iron pipe with 3" bronze cap stamped to indicated the corner position. He established the following reference objects: 8" Cedar - N 43° E - 25.3'; 5" Cedar - S 69° E - 12.6'; 7" Hemlock - S 06 E - 12.2'; 7' metal post & sign

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

N 89° E - 3.2'.

He recorded said corner in Liber 1, page 155 of Land Corners for Gogebic County. Found Richard Drahn corner monument and witnesses.

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2½" iron pipe and 3" bronze cap which read: T.46 N., R.43-44 W.; M.C.; S-25, S-30, R.L.S. 21 564; 1975, from which I established the Existing and new bearing trees and reference objects.

12" Cedar N 43° E 25.26'  
7" Cedar S 69° E 12.26'  
9" Hemlock S 06° E 12.19'  
8" Cedar S 34° E 7.41'  
7' metal post & sign N 89° E 3.20' (to face)

**BERE GROUP APPROVED**  
Richard P. Drahn 10/10/97  
**COUNTY REPRESENTATIVE**



( all measurements are to nail in side of tree )

Signed by John P. Goss  
Surveyor's Michigan License No. 23509  
Fed. No. TV - 25

Date October 1, 1997