

SEP 08 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Gogebic  
 (County)

Located In:

Corner Code #

1. Public Land Survey

T46 N R 44 W      A-2  
 T \_\_\_\_\_ R \_\_\_\_\_

T46 N R 45 W      M-2  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 6 & 1; T.46 N., R.44-45 W.

I, Richard L. Drahn in a field survey on April 4, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on August 30, 1847. Original B.T.s --- 24" Yellow Birch S.70 E. 25 links (16.50') --- 8" Fir N.29 W. 16 links (10.56') --- Corner restored by Richard L. Drahn on 5/11/83 from the remains of the Y. Birch B.T. and from recovered natural feature ties north and south and a line tree north. He set a 2' X 30" aluminum pipe with a 3 $\frac{1}{2}$ " stamped aluminum cap and the following new B.T.s:

12"	Sugar Maple	N.66 W.	27.62'
7"	Sugar Maple	N.78 E.	18.13'
8"	Sugar Maple	S.37 W.	33.18'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6'	steel sign rail East	1.6'
----	----------------------	------

Corner recorded in Gogebic County Liber 2, Page 529 on 1/26/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

16"	Sugar Maple	N.67 W.	27.34'	(new nail)
11"	Sugar Maple	N.76 E.	18.12'	" "
9"	Sugar Maple	S.37 W.	33.16'	" "
6'	Steel sign rail	N.87 E.	1.58'	

The original Y. Birch B.T. is now a badly decayed Y. Birch stump

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

10"	Sugar Maple	S.42 E.	25.16'
-----	-------------	---------	--------

**PEER GROUP APPROVED**  
Richard L. Drahn 5/13/98  
**COUNTY REGISTRAR**

Register's Office  
 Gogebic County

Received for record the  
14<sup>TH</sup> day of MAY  
 A. D. 1998 at 3:00 o'clock  
P M., and recorded in  
 Liber 6 of CORNERS  
 on page 346  
Raymond Collins Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Richard L. Drahn

Date April 12, 1998

Surveyor's Michigan License No. 21564