

**SURVEY &
REMONUMENTATION**

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in SECTION
Gogebic
(County)

Located In: Corner Code #

Received for record the
14TH day of MAY
A. D. 1998 at 3:10 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 347
Ramona Collins, Deputy
Register of Deeds

- | | | |
|------------------------------------|---------------------------|-----|
| 1. Public Land Survey | T <u>46N</u> R <u>44W</u> | A-3 |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T <u>46N</u> R <u>45W</u> | M-3 |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 6, 7, 1 & 12; T.46 N., R.44-45 W.

I, Richard L. Drahn in a field survey on April 11, 1998
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3	7	8	9	10	11	12							
4	18	17	16	15	14	13							
5													
6	19	20	21	22	23	24							
7													
8	30	29	28	27	26	25							
9													
10	31	32	33	34	35	36							
11													
12													
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/30/1847. Original B.T.s --- 10" Fir S.36 E. 16 links (10.56') --- 14" Hemlock N.48 W. 11 links (7.26') --- 10" Cedar S.22 W. 14 links (9.24') --- 10" Spruce N.25 E. 19 links (12.54') ---

Corner restored by Richard L. Drahn on 5/11/83 from the stump remains of the Hemlock and the stump holes of the Cedar and Spruce B.T.s, and from line trees, natural feature ties and recovered corners north, south, east and west. He set a 3/4" X 48" solid aluminum rod with a 3/4" stamped aluminum cap and the following

- | | | | |
|-----|-------|---------|--------|
| 6" | Cedar | N.53 W. | 16.42' |
| 11" | Cedar | N.55 E. | 18.86' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | | | |
|----|-----------------|---------|--------|
| 8" | Cedar | S.04 E. | 45.80' |
| 6' | Steel sign rail | S.88 E. | 1.4' |

Corner recorded in Gogebic County Liber 2, Page 531 on 1/26/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- | | | | |
|--------------------|---------|--------|------------|
| 7" Cedar | N.53 W. | 16.45' | |
| 15" Cedar | N.53 E. | 18.50' | (new nail) |
| 9" Cedar | S.05 E. | 45.41' | (new nail) |
| 6' Steel sign rail | S.89 E. | 1.42; | |

Only shallow depressions remain of the last three original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- | | | | |
|-----|-------|---------|--------|
| 10" | Cedar | N.06 W. | 14.95' |
|-----|-------|---------|--------|

PEER GROUP APPROVED

Richard L. Drahn 5/19/98
COUNTY REGISTER



Signed by Richard L. Drahn Date April 12, 1998

Surveyor's Michigan License No. 21564