

**SURVEY & REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**  
 For corners in

|   |                           |                |
|---|---------------------------|----------------|
| <u>Gogebic</u><br><small>(County)</small> | Located In:               | Corner Code #: |
| 1. Public Land Survey                     | T <u>46N</u> R <u>44W</u> | <u>A-4</u>     |
|   | T _____ R _____           | _____          |
|   | T <u>46N</u> R <u>45W</u> | <u>M-54</u>    |
|   | T _____ R _____           | _____          |
| 2. Property Controlling in Section        | S _____ T _____ R _____   | _____          |
|   | S _____ T _____ R _____   | _____          |
| 3. Miscellaneous Property in Sec.         | S _____ T _____ R _____   | _____          |
|   | S _____ T _____ R _____   | _____          |

Register's Office }  
 Gogebic County } ss.

Received for record the  
14<sup>TH</sup> day of MAY  
 A. D. 1998 at 3:10 o'clock  
7 m., and recorded in  
 Liber 6 of CORNERS  
 on page 348  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 7 & 12, T.46 N., R.44-45 W

I, Richard L. Drahn, in a field survey on April 11, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Austin Burt on 8/30/1847. Original B.T.s --- Hemlock 30" S.35 E. 26 links (17.16') --- Hemlock 12" N.35 W. 45 links (29.70') ---

Corner restored by Richard L. Drahn, 21564, on 5/11/83 from the remains of the two original B.T.s, and recovered line trees north and south. He set a 2" X 30" aluminum pipe with a 3/4" stamped aluminum pipe and the following:

- |    |                 |         |        |
|----|-----------------|---------|--------|
| 9" | Sugar Maple     | N.36 W. | 18.61' |
| 7" | White Ash       | N.59 E. | 32.19' |
| 8" | Sugar Maple     | S.20 W. | 21.14' |
| 6' | Steel sign rail | N.81 E. | 1.7'   |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Corner recorded in Gogebic County, Liber 2, Page 533 on 1/26/84.

Corner research on file with Gogebic County records.

A stump hole with fragments of hemlock wood and bark are all that remain of the original SE bearing tree, and a stump hole remains of the NW B.T.

Recovered the monument as described and the bearing trees as follows:

- |     |                 |         |                  |
|-----|-----------------|---------|------------------|
| 12" | Sugar Maple     | N.36 W. | 18.80 (new nail) |
| 9"  | White Ash       | N.58 E. | 32.19' " "       |
| 10" | Sugar Maple     | S.18 W. | 21.13'           |
| 6'  | Steel sign rail | N.80 E. | 1.77'            |

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

New bearing tree referenced:

- |    |             |         |        |
|----|-------------|---------|--------|
| 9" | Sugar Maple | S.88 W. | 12.69' |
|----|-------------|---------|--------|

**NEED GROUP APPROVAL**  
Richard L. Drahn 5/13/98  
**COUNTY REGISTER**



Signed by Richard L. Drahn Date April 12, 1998

Surveyor's Michigan License No. 21564