SEP 0 8 1998

SECTION

For corners in

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

	Strate 2 Offich (
	Gogebic County Ss.
TE	Received for ment a
70	day of Junia
	19-70. 11 1. 20 o'clock
	Liber 7 of Conner
	🖿 hage 🛴
	Rumonal Collins, Old
	Register of Dunde
Da-:-4a	or of Doods Character & File Northern
negiste	r of Deeds Stamp & File Number

Register's acc)

Gogebic (County)		Located In:	Corner Code ##			
1.º Pub	olic Land Survey	146N R 44W	A-6			
		T R T <u>46N</u> R <u>45</u> W.	M-6			
	perty Controlling Section	S T R S T R				
	cellaneous perty in Sec.	S T R S T R				

4. Lot No. $_$, Recorded Plat $_$ 5. Private Claims _

½ Corner, 18 & 13€; T.46 N., R.44-45 W.

Richard L in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	<u> </u>	8	С	D	Е	F	G	H	j	K	L	<u> </u>
2	L	6		j 5		_] -	;			
3		L		<u></u>		<u> </u>						
4	L	 7	<u> </u>	 8—	_	 	<u>_</u> 1	0-	_,		1	2
5			_	<u> </u>		$oldsymbol{ol}}}}}}}}}}}}}}}}}}$				L		
6	_1	 8—	ļ_,	ا سر	<u>_</u> ,	 6	L	5	1	_	_,	34
7		<u> </u>	<u> </u>	<u> </u>	ļ	ļ	ļ					
8	<u> </u>	<u> </u>	2	<u>.</u> 0—	<u> </u> _2	1	├ _2	2—	2	3	_2	4
9	<u> </u>	<u> </u>	<u> </u>	 	_	 	-	<u> </u>				
10	3	0—	L _2	9	L2	8	<u> </u> _2	7	L_2	6—	<u>_</u> 2	5
11	<u> </u>	_	<u> </u>	<u> </u>	_	<u> </u>	<u> </u>			L		
12	3	 }1—	 		_ 3	 3—	<u> </u>	4	 -3	5	<u>3</u>	6
13			1					1				

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/30/1847. Original B.T.s --- Y. Birch 18" S.32 W. 27 links (17.82') --- Y. Birch 30" N.82 E. 44 links (29.04') ---

Corner restored by Richard L. Drahn (21564) on 5/25/83, from the remains of the two original B.T.s. He set a 2" X 30" aluminum pipe with a $3\frac{1}{4}$ " stamped aluminum cap and the following new B.T.s:

10" N.28 W. 25.47' Sugar Maple Sugar Maple 7" N.67 E. 50.32' 17" **Hemlock** S.10 E. 58.921

S.87 E. 6 ' Steel sign rail 2.41

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 2, Page 537 on 1/26/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

25.47' (new nail) N.30 W. 13" Sugar Maple 10" Sugar Maple 50.33' N.66 E. 20" 58.92' S.15 E. Hemlock

Steel sign rail S.89 E. 2.361

Badly decayed Yellow Birch stumps still remain from the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

11" Sugar Maple S.75 W. 17.18'

PEER GROUP APPROVE



__ Date <u>June 11, 1998</u>

Surveyor's Michigan License No. _ 21564... FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983