

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

GOGEBIC COUNTY

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46</u> N. <u>X.</u> , R. <u>44</u> W.	A-11
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____	PEER GROUP	Approved
5. PRIVATE CLAIMS _____	<i>Richard L. Drahn</i> <u>1/20/94</u>	_____
Section corner 30, 31, 25 and 36; T46N, R44-45W.		

Register's Office }
Gogebic County } ss.

Received for record the
5TH day of JANUARY
A. D. 1994 at 10:06 o'clock
A m., and recorded in
Liber _____ of _____
on page 351
Betty Sassin, Deputy
Register of Deeds

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Richard L. Drahn do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram — over) were, in a field survey on June 16 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt, U.S. Deputy Surveyor on August 30, 1847.

Original bearing trees:

Fir	10"	S.63 1/2° E.	31 links	(20.46 feet)
Fir	12"	N.59° W.	17 links	(11.22 feet)
Y. Birch	20"	S.86° W.	21 links	(13.86 feet)
Fir	8"	N.53° E.	33 links	(21.78 feet)

22.91 chains north "Y. Birch 18" diameter" line tree.
No record of subsequent corner restoration found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
No evidence remains of the fir bearing trees. Restored corner position by proportionate measurement from G.L.O. 1/4 north 40 chains, through recovered line tree stump at 22.91 chains north, to corner location. At a point S.86°W., 13.9 feet from the restored location I recovered the badly decayed remains of a very large wind-thrown yellow birch. Corner location lays within 1.6 feet of a single proportionate analysis of the west range line of T.46N., R.44W. No evidence found of subsequent corner restoration.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
At the corner position I set a standard 2 1/2" diameter by 30" long split base aluminum monument with a 3" cast aluminum cap, stamped to read: T46N, R44-45W; S-30, S-31, S-25, S-36; 1993; R.L.S. 21564. From which I have established the following new blazed and scribed bearing trees:

10"	Sugar Maple	N.23°E.	10.50 feet
11"	Red Maple	S.47°E.	25.81 feet
6"	Sugar Maple	N.82°W.	22.02 feet
6'	Steel rail	N.81°E.	1.48 feet

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Richard L. Drahn CHIEF OF SURVEY PARTY DATE December 20, 1993
MICHIGAN REGISTERED LAND SURVEYOR



FED. V-1

SURVEYOR'S MICHIGAN REGISTRATION NO. 21564