

**SURVEY &  
REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
Gogebic County } ss.

Received for record the  
18<sup>th</sup> day of JUNE  
A. D. 1998 at (1:25) o'clock  
P m., and recorded in  
Liber 7 of CORNERS

on page 4  
Ramona L. Collins, Dep.  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in SECTION

Gogebic	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>46N</u> R <u>44W</u>	<u>B-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 7 & 18; T.46 N., R.44 W.

Richard L. Drahn, in a field survey on June 8, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5	●											
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/16/1851. Original B.T.s --- Cedar 12" S.20 E. 15 links (9.9') --- Cedar 12" N.12 W. 15 links (9.9') ---

J. Davis on 1/4/37, recovered both original B.T.s still scribed and placed a location poster on the northerly one.

Richard L. Drahn (21564) on 11/1/74 recovered both bearing trees, one a 20" live Cedar with scribing still visible. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new bearing trees:

- 6" Yellow Birch N.06 E. 37.6'
- 7" Yellow Birch S.42 E. 13.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 5" Red Maple S.23 W. 34.4'
- 4" X 4" X 7' Cedar Post N.34 W. 3.8'

Corner recorded in Gogebic County in Liber 1, Page 271 on 3/4/77.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- 7" Yellow Birch N.06 E. 37.50' (new nail)
- 12" Yellow Birch S.42 E. 13.14' " "
- 8" Red Maple S.23 W. 34.65' " "
- 4" X 4" Cedar sign post N.36 W. 3.52'

The first original B.T. is almost completely decayed. The second on is now a

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

live 23" Cedar with scribing still visible.

New bearing objects referenced:

- 6" Black Ash N.75 E. 32.05'
- 6' Steel sign rail S.72 E. 2.08'

**PEER GROUP APPROVAL**

Richard L. Drahn 6/17/98  
COUNTY SURVEYOR



Signed by Richard L. Drahn Date June 11, 1998

Surveyor's Michigan License No. 21564