

SURVEY & MONUMENTATION

JAN 05 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Code #	<u>Gogebic</u> (County)	Located in:	Corner
1. Public Land Survey		T <u>46N</u> R <u>44 W.</u>	<u>B-7</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

Received for record the
26th day of MAY
A. D. 1902 at 10:35 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 280
Henry Rupp
Dep't, Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner 18 & 19; T.46 N., R.44 W.

I, Richard L. Drahn, in a field survey on April 27, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7		●											
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt on 7/18/1851. Original bearing trees:
Tamarack 8" S.32° W. 30 links (19.80')
Tamarack 8" N.14° E. 23 links (15.18')

J. Davies, on 12/18/36 recovered a scribed B.T. and placed a location poster on a 12" Tamarack.

Corner restored by Richard L. Drahn on 10/18/74 from the two blazed and scribed original B.T.s. He set a 2" X 5' iron pipe monument with a 3" stamped brass cap and the following new bearing trees:

Cedar 7" N.65° E. 70.5'
Cedar 9" S.44° E. 33.7'
Tamarack 8" S.85° W. 52.5'
4"X4"X7' Cedar sign post N.46° W. 2.5'

Corner recorded in Gogebic County Liber 1, Page 272 on 3/4/77.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:
Cedar 8" N.65° E. 70.47' (new nail)
Cedar 10" S.44° E. 33.66' (new nail)
Tamarack 11" S.83° W. 52.55' (new nail)
4"X4"X7' Cedar sign post N.42° W. 2.23'

The original SW B.T. is now a badly decayed Tamarack stump; the NE B.T. is now a 3' Tamarack stub with portions of the B.T. blaze.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing object referenced:
Steel sign rail 7' S.03° E. 1.82'



PEER GROUP APPROVED
Richard L. Drahn 05/24/00
COUNTY REGISTRAR

Signed by Richard L. Drahn Date April 28, 2000

Surveyor's Michigan License No. 21564
USFS N-3