

**SURVEY & REMONUMENTATION**

NOV 12 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogetic County } ss.

For corners in

Gogetic  
(County)

Located In:

Corner Code #

1. Public Land Survey

T	46NR	44W	C - 1
T	47NR	44W	C - 13
T	_____	_____	_____
T	_____	_____	_____
S	_____	_____	_____
S	_____	_____	_____
S	_____	_____	_____
S	_____	_____	_____

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Received for record the  
18<sup>th</sup> day of SEPTEMBER  
A. D. 1997 at 10:45 o'clock  
A m., and recorded in  
Liber 6 of CORNSES  
page 200  
Kamera Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Goss, in a field survey on Aug. 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Sec. cor, comm. to sec's 5,6, 31 & 32

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt in 1847.  
Original bearing trees: Maple 14" N 62°E 43 links  
S. Maple 12"N 21°W 25 links  
Y. Birch 12"S 73°E 23 links  
Y. Birch 14"S 32°W 36 links.

On October 2, 1970, Donald D. Lappala, RLS, restored corner at record bearing and distance from the 4 original bearing trees or their stump. He set a 2½" Iron pipe with 3" bronze tablet which indicated corner position. He established the following bearing trees: 10" Sugar Maple - N 34° E - 31.5'; 6" Sugar Maple -

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
S 30° E - 6.5'; 8" Sugar Maple - S 70° W - 18.5'.  
Corner recorded in USFS Liber Z-5 on August 10, 1972.

Found Donald D. Lappala, monument and witnesses.  
I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2½" Iron pipe with 3" bronze Tablet which reads: T. 46-47 N., R. 44 W.; S-5, S-6, S-31, S-32; R.L.S. 12585; 1970, from which I established existing and new bearing trees and reference object.

12" Sugar Maple N 34° E 31.57'  
9" Sugar Maple S 30° E 6.40'  
11" Sugar Maple S 80° W 18.35'  
6" Cherry N 41° W 13.54'  
6" Rail & sign N 05° W 1.5' (to face)

(All measurement to nail in side of tree)

PEER GROUP APPROVED

Richard P. Dehn 9/17/97  
COUNTY REPRESENTATIVE



Signed by John P. Goss

Date August 29, 1997

Surveyor's Michigan License No. 23509

Fed. No. 205