

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in

Gogebic Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T46 N R44 W. C-4
 T _____ R _____
 T _____ R _____ **SURVEY &**
 T _____ R _____ **REMONUMENTATION**

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____ **JAN 05 2001**

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____ **SECTION**

Received for record the
26TH day of MAY
 A. D. 2000 at 10:35 o'clock
A m., and recorded in
 Liber 7 of CORNUS
 page 204
Cheryl Ruppel
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner 7 & 8; T.46 N., R.44 W.

I, Richard L. Drahn, in a field survey on May 6, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		●	8		9		10		11		12	
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 8/13/1851. Original bearing trees:

Fir	8"	S.54° W.	8 links	(5.28')
Maple	11"	N.65° E.	34 links	(22.44')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Restored corner position at record bearing and distance from the remains of the original Red Maple bearing tree. It is now a large Red Maple stump decayed to well below ground line. Old stump has an 11" Red Maple sprout. No evidence remains of the Fir bearing tree remains.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner location I set a 2" X 30" aluminum pipe monument with a 3 1/4" aluminum cap stamped to indicate the corner position. From the monument I set the following new, scribed bearing trees:

Red Maple	8"	N.58° W.	27.41'
Red Maple	11"	N.62° E.	24.61'
Red Maple	9"	S.46° W.	17.84'
Steel sign rail	6'	S.86° E.	2.53'

DEED GROUP APPROVED
Richard L. Drahn 05/24/00
 COUNTY REGISTER



Signed by Richard L. Drahn Date May 12, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995