

**SURVEY &
REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }
Gogebic County } ss.

Received for record the
14th day of MAY
A. D. 1998 at 3:10 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 350
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> SECTION <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>44W</u>	<u>C-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 7, 8, 17 & 18; T.46 N., R. 44 W.

I, Richard L. Drahn in a field survey on May 6, _____, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/13/1851. Original B.T.s --- Sugar 8" S.43 E. 14 links (9.24') --- Sugar 8" N.67 W. 25 links (16.50.) --- L. Chantalois on 11/15/35, recovered a scribed Y. Birch witness tree. Richard L. Drahn (21564) on 11/1/74 restored the corner from the remains of the two original B.T.s, the GLO witness tree and from Chantalois B.T. He set a 2½" X 60" iron pipe with a 3" stamped brass cap and the following:

13"	Cedar	N.51 W.	40.9'
4"	Sugar Maple	S.57 E.	13.2'
8"	Sugar Maple	S.33 W.	32.7'
4" X 4" X 7'	Cedar sign post	bears S.06 E.	3.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County, USFS Liber, Page J-5 on 1/6/75. Certificate re-issued on 3/4/77 in Liber 1, Page 273.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

13"	Cedar (dead)	N.52 W.	40.73 (new nail)
5"	Sugar Maple	S.57 E.	13.24' " "
11"	Sugar Maple	S.31 W.	32.80' " "
4" X 4"	Cedar sign post	S.06 E.	3.14'

Stump holes are all that remain of the original B.T.s. The Yellow Birch witness tree is now a Yellow Birch stump decayed to groundline.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced

10"	Sugar Maple	N.50 W.	26.15'
6'	Steel sign rail	N.22 E.	2.46'

PEER GROUP APPROVED

Richard L. Drahn 5/13/98
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date May 10, 1998

Surveyor's Michigan License No. 21564