

**SURVEY &  
REMONUMENTATION**

SEP 08 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>44W</u>	<u>C-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County } ss.

Received for record the  
23<sup>RD</sup> day of JULY  
A. D. 1998 at 11:35 o'clock  
A m., and recorded in  
Liber 7 of CORNERS  
on page 17  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 17 & 18; T.46 N., R.44 W.

Richard L. Drahn, in a field survey on July 17, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Austin Burt on 8/13/1851. Original B.T.s --- Sugar 12" S.70 E. 22 links (14.52') --- Hemlock 10" N.50 W. 38 links (25.08)

Corner position restored by Richard L. Drahn (21564) on 11/4/74 from the remains of the two original B.T.s and from line trees recovered N & S. He set a 2 $\frac{1}{4}$ " X 5' iron pipe with a 3" stamped brass cap and the following:

6"	Yellow Birch	N.82 W.	19.3'
6"	Sugar Maple	N.82 E.	33.9'
3"	Yellow Birch	S.05 W.	19.8'
4" X 4" X 7'	Cedar post	S.78 W.	3.0'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Corner recorded in Gogebic County Liber 1, Page 274 on 3/4/77.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

9"	Yellow Birch	N.82 W.	19.21' (new nail)
10"	Sugar Maple	N.85 E.	33.91' " "
4"	Yellow Birch	S.04 W.	dead and down
4" X 4"	Cedar post	S.80 W.	2.75'

A stump hole from the original Sugar B.T. and a badly decayed Hemlock stump still remain from the original bearing trees.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

New bearing objects referenced:

10"	Sugar Maple	S.02 W.	9.48'
6'	Steel sign rail	N.02 W.	1.88'

Resource grade GPS: Lat 46-23-00.81 N  
Long 89-50-40.87 W

**PEER GROUP APPROVED**

Richard L. Drahn 7/22/98  
CO-SITE



Signed by Richard L. Drahn Date July 19, 1998

Surveyor's Michigan License No. 21564