

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office
 Gogebic County } ss.

For corners in

Gogebic Located In: Corner Code #
 (County)

1. Public Land Survey T46 N R44 W C-8
 T ___ R ___
 T ___ R ___ **SURVEY &**
 T ___ R ___ **REMONUMENTATION**

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___ **JAN 05 2001**

3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___ **SECTION**

Received for record the
26th day of MAY
 A. D. 2000 at 10:35 o'clock
A m., and recorded in
 Liber 7 of CORNES
 on page 205
Cheerl Ruppel
 Dep. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner 19 & 20; T.46 N., R.44 W.

I, Richard L. Drahn, in a field survey on April 27, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by Austin Burt on 8/17/1851. Original bearing trees:

Hemlock	10"	N.65 W.	18 links	(11.88')
Sugar	14"	S.46 E.	15 links	(9.90')

Corner position restored by Richard L. Drahn, RLS 21564 on 5/25/83 from the remains of the two original B.T.s, a natural feature tie north and retracement measurement north and south to recovered section corners. He set a 30' aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing trees:

Sugar Maple	12"	N.41 W.	11.95'
Sugar Maple	8"	N.80 E.	38.75'
Sugar Maple	9"	S.18 E.	39.84'
Steel sign rail	6'	N.03 W.	1.44'

Corner recorded in Gogebic County Liber 2, Page 542 on 1/26/84.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

Sugar Maple	13"	N.38 W.	12.04'	(new nail)
Sugar Maple	8"	N.82 E.	38.71'	(new nail)
Sugar Maple	9"	S.17 E.	39.81'	(new nail)
Steel sign rail	6'	N.05 W.	1.46'	

Fragments of decayed Hemlock wood still remain from the NW original B.T. and a stump hole remains from the SE B.T..

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:
 Sugar Maple 10" S.66 W. 27.49'

PEER GROUP APPROVAL
Richard L. Drahn 05/24/00
 COUNTY REGISTER & TAKER

Signed by Richard L. Drahn Date April 28, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983
 REVISED OCT., 1996