

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
 Gogebic County } 53.

For corners in

Gogebic Located In: Corner Code #
 (County)

1. Public Land Survey T46 N R44 W. C-9
 T___ R___
 T___ R___ **SURVEY &**
 T___ R___ **MONUMENTATION**

2. Property Controlling S___ T___ R___
 in Section S___ T___ R___ **JAN 05 2001**

3. Miscellaneous S___ T___ R___
 Property in Sec. S___ T___ R___ **SECTION**

Received for record the
26th day of MAY
 A. D. 1900 at 10:40 o'clock
A m., and recorded in
 Liber 7 of CORNGES
 page 286
Cheryl Ruspe
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 19,20,29 & 30; T.46 N., R.44 W

I, Richard L. Drahn, in a field survey on April 27, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 8/12/1851. Original bearing trees:

Cedar	14"	S.61° E.	40 links	(26.40')
Cedar	12"	N.59° W.	57 links	(37.62')

On 11/12/35, L. Chantelois recovered a scribed Birch witness tree. He placed a location poster on a 13" Hemlock.

Corner restored by Richard L. Drahn, RLS 21564 on 5/26/83 from the shallow stump holes of the two original B.T.s, recovered line trees east and west and retracement measurements north, east and west to recovered 1/4 corners. He set a 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing trees:

Sugar Maple	16"	N.35° E.	29.30'
Sugar Maple	9"	S.86° E.	14.82'
Sugar Maple	13"	S.40° W.	29.92'
Steel sign rail	6'	N.05° W.	1.35'

Corner recorded in Gogebic County Liber 2, Page 545 on 1/26/84.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

Sugar Maple	19"	N.37° E.	29.12'	(new nail)
Sugar Maple	13"	S.85° E.	14.75'	(new nail)
Sugar Maple	17"	S.42° W.	30.22'	(new nail)
Steel sign rail	6'	N.05° W.	1.33'	

Stump holes remain from the two original B.T.s, the original Y. Birch witness tree is now a very badly decayed stump and Chantelois's tag tree is now a downed and decayed 12-14" Hemlock.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

Sugar Maple	8"	S.15° E.	19.29'
-------------	----	----------	--------

PEER GROUP APPROVED

Richard L. Drahn 05/24/00
 COUNTY REPRESENTATIVE

Signed by Richard L. Drahn Date April 28, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN., 1983

REVISED OCT., 1996