

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
18TH day of SEPTEMBER
A. D. 1997 at 10:45 o'clock
A m., and recorded in
Liber 6 of CORNERS

on page 203
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code #

1. Public Land Survey

T46NR 44W D-1
T47NR 44W D-13

T R
T R

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John P. Goss, in a field survey on Aug. 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 cor. comm. to sec's. 5 & 32

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt in 1847.
Original bearing trees: Spruce N 37° W 41 links
White Pine N 76° E 37 links

On October 5, 1970, Donald D. Lappala, RIS, restored corner position at record bearing and distance from the two original bearing trees: A large decayed spruce stump and a 30" decayed white pine stump with scribed visible. He set a 2 1/2" iron pipe with 3" cap and new B.T. - 12" Black Spruce N 33° W- 23.0'; 9" Cherry- N 13° E - 38.2'; 4" White Spruce- S 26° W- 10.3'. Corner recorded in USFS Liber Z-7, on August 10, 1972.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In 1992 a 4" by 4" wood post North and a 3" Maple- N 59° W- 22.96' was added. Recovered the monument as described above and 2 bearing trees and 1 stump. Also recovered a large spruce stump from original bearing trees;

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED
Richard P. Dean 9/17/97
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2 1/2" iron pipe with 3" bronze cap which reads: T. 46-47 N., R.44 W.; 1/4; S-5, S-32; R.L.S. 12585; 1970, from which I established the existing and new bearing trees and reference objects:

12" Black Spruce (stump) N 33° W 23.0'
12" Cherry N 13° E 38.23'
9" White Spruce S 26° W 10.35'
4" Maple N 59° W 22.90'
4"x4" wood post & sign N 30° W 1.15' (to face)
6' Rail and sign Due S. 1.57' (to face)
(measurement to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date August 18, 1997

Fed. No. Z-7