

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
 (County)

Located In:

Corner Code #

1. Public Land Survey

T46 N R44 W.

D-3

T _____ R _____

T _____ R _____

T _____ R _____

**SURVEY &
 REMONUMENTATION**

2. Property Controlling
 in Section

S _____ T _____ R _____

S _____ T _____ R _____

JAN 05 2001

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 Corner 5 & 8; T.46N., R.44 W.

I, Richard L. Drahn, in a field survey on May 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 8/22/1851. Original bearing trees:

Cedar	6"	S.19° E.	23 links	(15.18')
Y. Birch	7"	N.07° W.	29 links	(19.14')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Restored corner position at record bearing and distance from the remains of the two original bearing trees. The first is a windthrown shallow depression. The second one is now a large, very badly decayed Yellow Birch stump with portions of Y. Birch wood, roots and bark. This is the only old growth Yellow Birch remains recovered in the area. The "enter swamp, N-S" 5.40 chains east checks to within 5 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Tamarack	7"	N.70° E.	18.42'
Cedar	10"	North	20.21'
Cedar	6"	S.69° W.	17.18'
Steel sign rail	6"	N.42° E.	2.24'

DEER GROUP APPROVED

Richard L. Drahn 05/24/00
 COUNTY SURVEYOR



Signed by Richard L. Drahn Date May 12, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN. 1983
 REVISED OCT., 1995

USFS E-7

Register's Office
 Gogebic County

Received for record and
26th day of MAY
 A. D. 2000 at 10:40 o'clock
A M., and recorded in
 Liber 7 of CORNERS
 # page 287
Cheeryl Ruppe
 Dep. Register of Deeds

Register of Deeds Stamp & File Number

