

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }
 Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T46 N R44 W.	<u>E-2</u>
	T ___ R ___	SURVEY &
	T ___ R ___	MONUMENTATION
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	<u>JAN 05 2001</u>
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	<u>SECTION</u>
	S ___ T ___ R ___	

Received for record the
26TH day of MAY
 A. D. 2000 at 10:40 o'clock
A m., and recorded in
 Liber 7 of CORNERS
 on page 291
Cheryl Ruppe
 Dep. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 1/4 Corner 4 & 5; T.46 N., R.44 W.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5	●	4		3		2			1
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

I, Richard L. Drahn, in a field survey on April 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by Austin Burt on 8/14/1851. Original bearing trees:
 Hemlock 12" S.09 E. 12 links (7.92')
 Hemlock 14" N.40 W. 5 links (3.30')

Corner restored by Richard L. Drahn, RLS 21564 on 11/2/81 from the remains of the two original B.T.s, (the SE B.T. was still scribed). He set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s"
 Cedar 5" N.25 W. 28.68'
 Cedar 6" N.59 E. 23.79'
 Red Maple 5" S.08 W. 19.80'
 Steel sign rail 6' N.04 E. 1.7'

Corner recorded in Gogebic County Liber 2 Page 216 on 3/10/82.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:
 Cedar 10" N.26 W. 28.96' (new nail)
 Cedar 7" N.57 E. 23.82' (new nail)
 Red Maple 8" S.07 W. 19.78' (new nail)
 Steel sign rail 6' N.04 E. 1.72'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:
 Twin Red Maple 6" N.82 W. 4.97'

PEER GROUP APPROVED
Richard L. Drahn 05/24/00
 COUNTY REGISTRAR



Signed by Richard L. Drahn Date April 30, 2000

Surveyor's Michigan License No. 21564