

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in

Gogebic Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T46 N R44 W. E-6
 T ___ R ___ SURVEY &
 T ___ R ___ MONUMENTATION
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___ JAN 05 2001

3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___ SECTION

Received for record the
26th day of MAY
 A. D. 2000 at 10:40 o'clock
A m., and recorded in
 Liber 7 of CORNERS
 on page 294
Cheryl Rupp
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 1/4 Corner 16 & 17; T.46 N., R.44 W.

I, Richard L. Drahn, in a field survey on April 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by Austin Burt on 8/14/1851. Original bearing trees:
 Sugar 14" S.48° W. 20 links (13.20')
 Sugar 7" N.60° E. 7 links (4.62')

Corner restored by Richard L. Drahn, RLS 21564 on 9/17/81 from the remains of the two original B.T.s and natural feature ties north and south. He set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s:
 Sugar Maple 9" N.73° W. 32.90'
 Sugar Maple 7" N.32° E. 10.51'
 Sugar Maple 12" S.38° E. 19.48'
 Steel sign rail 6' N.35° E. 1.6'

Corner recorded in Gogebic County Liber 2, Page 218 on 3/10/82.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:
 Sugar Maple 13" N.73° W. 32.11' (new nail)
 Sugar Maple 10" N.31° E. 10.46'
 Sugar Maple 14" S.37° E. 19.48'
 Steel sign rail 6' N.35° E. 1.53'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 New bearing tree established:
 Sugar Maple 5" S.17° W. 38.20'

DEED GROUP APPROVED
Richard L. Drahn 05/24/00
 COUNTY REGISTER & TIME



Signed by Richard L. Drahn Date May 2, 2000
 Surveyor's Michigan License No. 21564