

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ON.

For corners in

Gogebic Located In: Corner Code #  
(County)

1. Public Land Survey T46 N R44 W. E-8  
T R  
T R  
T R **SURVEY & MONUMENTATION**

2. Property Controlling in Section S T R  
S T R

3. Miscellaneous Property in Sec. S T R  
S T R

**JAN 05 2001**

**SECTION**

Received for record the  
26<sup>th</sup> day of MAY  
A. D. 2000 at 10:40 o'clock  
1 m., and recorded in  
Liber 7 of CORNERS

page 296  
*Robert Ruppel*  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
1/4 Corner 20 & 21; T.46 N., R.44 W.

I, Richard L. Drahn, in a field survey on May 6, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Original corner established by Austin Burt on 8/13/1851. Original bearing trees:

Cedar	10"	S.60° E.	24 links	(15.84')
Cedar	12"	N.56° W.	22 links	(14.52')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Corner research on file with Gogebic County records.  
Restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a large, shallow, windthrown depression. The second one is now a very badly decayed 16-20" downed Cedar with portion of the B.T. blaze overgrowth still visible. The 1.095 chain distance south to "enter swamp, ESE" checks to within 4 feet. The 8.905 chain distance north to "leave swamp, NW" is indistinct but checks to timber type change.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
At the corner position I set a 3/4" X 4' aluminum rod monument with a 3 1/4" stamped aluminum cap and the Following new B.T.s (all measurements taken to a nail in side of tree:

Black Ash	7"	N.06° E.	13.14'
Yellow Birch	7"	S.46° E.	21.56'
Black Ash	6"	S.87° W.	18.08'
Steel sign rail	6'	N.42° W.	2.29'

PEER GROUP APPROVED  
*Richard L. Drahn* 05/24/00  
COUNTY SUPERVISOR



Signed by Richard L. Drahn Date May 12, 2000  
Surveyor's Michigan License No. 21564