

SURVEY & REMONUMENTATION

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Received for record the
8TH day of MAY
A. D. 1996 at 11:00 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 344
Richard L. Drahn, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #:	
1. Public Land Survey	T <u>47N</u> R <u>44W</u> .	<u>G-13</u>	
	T _____ R _____		
	T <u>46N</u> R <u>44W</u> .	<u>G-1</u>	
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. 33, 34, 3 & 4; T.47-46 N., R.44 W.

I, Richard L. Drahn in a field survey on May 6, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William A. Burt in 1847. Original B.T.s --- Cedar 8" N.37 E. 48 links (31.68') --- Y. Birch 14" N.06 W. 27 links (17.82') --- Cedar 10" S.13 W. 15 links (9.90') --- Y. Birch 8" S.55 E. 21 links (13.86').

Corner restored by Donald D. Lappala, RLS 12585 on 8/29/68 from the remains of all four B.T.s (SE Cedar scribed). He set a 2" x 5' iron pipe with a 3" stamped brass cap and the following new bearing trees: 7" (10") Y. Birch N.32 E. (N.35 E.) 26.1' (25.67") --- 8" Y. Birch (dead and down) S.47 E. (S.45 E.) 16.6' --- X chiseled in top of a 26" x 14" x 24" rock S.77 W. (S.79 W.) 12.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in USFS Liber, Page Z-13.

Recovered the monument as described and the bearing objects as noted in parentheses above. Fragments of cedar wood remain from the two original Cedars and depressions remain from the Yellow Birch B.T.s.

Act 74 research form on file with Gogebic County records.

PEER GROUP APPROVED
Richard L. Drahn 5/7/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

1" solid iron "1" rod	S. 52 W.	3.51'
4"x4" Cedar sign post	N. 54 E.	0.2'
6' Steel sign rail	S. 87 W.	2.6'
9" Sugar Maple	S. 25 E.	3.84'



Signed by Richard L. Drahn

Date May 7, 1996

Surveyor's Michigan License No. 21564