

Register's Office }
Sagebic County } ss.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Received for record the
26TH day of MAY
A. D. 19⁰⁰ at 10:40 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 302

Cheryl Ruppe
Dep. Register of Deeds

Register of Deeds Stamp & File Number

For corners in

GOGEBIC
(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R44W G-4

T___ R___
T___ R___ **SURVEY &**
T___ R___ **MONUMENTATION**

2. Property Controlling
in Section

S___ T___ R___
S___ T___ R___

JAN 05 2001

3. Miscellaneous
Property in Sec.

S___ T___ R___
S___ T___ R___

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter Corner, Sections 9 & 10, T46N, R44W

I, John P. Goss, in a field survey on April 26th 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 15, 1851.

Original bearing trees: Yellow Birch 14" S 37° E 41 links (27.06 ft.)
Sugar 6" N 58° W 13 links (8.58 ft.)

Richard L. Drahn, 21564, on Oct. 5, 1981, restored corner position at record bearing and distance from the remains of the two original bearing trees and other natural features calls. He set a 2" I.D. aluminum monument with 3/4" aluminum cap, stamped to indicated the corner position. He established the following reference objects: 9" S. Maple - N 34° W - 8.09 ft.; 7" S. Maple - East - 13.02 ft.; 14" Basswood - S 12° W - 12.03 ft.; 6' metal sign post - N 25° E - 1.75 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: On March 10, 1982, he recorded said corner in Liber 2, page 230 of Land Corners

No original evidence found.

Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

NEED GROUP APPROVED
Richard L. Drahn 05/24/00
COURT REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From found monument, stamped to read: T.46 N., R.44 W.; 1/4; S-9, S-10; 1981; R.L.S. 21564: from which I established the following existing and new reference objects:

11" Sugar Maple	N 34° W	8.09 ft.
8" Sugar Maple	East	13.02 ft.
15" Basswood	S 12° W	11.98 ft.
10" Maple	N 48° E	14.65 ft.
6' metal sign post	N 05° E	1.75 ft. to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date April 26, 2000

U.S.F.S. No. G-13