

**SURVEY &  
REMONUMENTATION**

OCT 03 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #:
1. Public Land Survey	T 47N R 44W.	H-13
	T R	
	T 46N R 44W.	H-1
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 Corner 34 & 3; T.46-47 N., R.44 W.

I, Richard L. Drahn, in a field survey on May 27, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Austin Burt on August 27, 1847. Original B.T.s --- Sugar Maple 9" N.42 E. 14 links (9.24') --- Sugar Maple 12" N.33 W. 61 links (40.26') --- Corner restored by Donald D. Lappala, RLS 12585 on 10/14/70 from the remains of the two original bearing trees, a line tree east and a natural feature tie west. He set a 2 1/2" iron pipe with a 3" stamped brass cap and the following new bearing trees: --- 7" (11") Red Maple S.70 W. (S.73 W.) 5.7' (5.71') --- 9" (11") Red Maple N.22 W. (N.19 W.) 37.3' (37.24') --- 7" (10") Sugar Maple N.45 E. (N.45 E.) 16.6' (16.73') --- Corner recorded in Gogebic County in USFS Liber, Page Z-15 on 5/27/70.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above.

Only depressions remain from the two original bearing tree.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Bearing objects referenced:

- 4" X 4" Cedar sign post S.61 E. 8.2'
- 6' Steel sign rail West 2.65'

Register's Office }  
Gogebic County } ss.

Received for record the  
10<sup>th</sup> day of JUNE  
A. D. 19 96 at 10:00 o'clock  
A m., and recorded in  
Liber 5 of COANGES  
page 382  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

PEER GROUP APPROVED  
Richard L. Drahn 6/6/96  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date May 29, 1996

Surveyor's Michigan License No. 21564