

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office  
 Gogebic County

Received for record the  
26<sup>th</sup> day of MAY  
 A. D. 2000 at 10:50 o'clock  
A m., and recorded in  
 Liber 7 of CORNERS  
 on page 307  
*Cheryl Ruspe*  
 Dep. Registrar of Deeds

For corners in  
GOGEBIC  
 (County)

Located In: Corner Code #

1. Public Land Survey T46NR 44 W H-3  
SURVEY &  
MONUMENTATION
2. Property Controlling in Section  
S T R  
S T R  
S T R  
S T R
3. Miscellaneous Property in Sec. JAN 05 2001  
SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Quarter Corner, Sections 3 & 10, T46N, R44W

John P. Goss in a field survey on April 10<sup>th</sup> 2000 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1							3		2			
2	6		5		4							1
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner established by Austin Burt, on August 22, 1851.  
 Original bearing trees: Sugar Maple 12" S 41° E 35 links (23.10 ft.)  
 Hemlock 7" N 29° W 30 links (19.80 ft.)  
 Richard L. Drahn, 21564, on April 13, 1982, restored corner position on line an equal distance between the Southwest and Southeast section corners. He set a 2" I.D. aluminum monument with a 3/4" aluminum cap, stamped to indicated the corner position. He established the following reference objects: 11" Aspen N 33° W - 40.25 feet; 12" Aspen ( now stub) - S 75° E - 44.05 ft.; 9" Aspen S 60° W - 18.75 ft.; 6' metal sign post - S 44° W - 2.5 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 On March 15, 1983, he recorded said corner in Liber 2, Page 378 of Land Corners  
 Found D. Drahn, monument and accessories.  
 Act 74 research on file.

DEED GROUP APPROVAL  
*Richard L. Drahn 05/24/00*  
 COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 From the found monument stamped to read: T.46 N., R.44.; 1/4; S-3, S-10; 1982;  
 R.L.S. 21564: from which I established the following existing and new reference objects:

- |                    |         |                    |
|--------------------|---------|--------------------|
| 14" Aspen          | N 33° W | 40.25 ft.          |
| 13" Aspen          | S 60° W | 18.60 ft. new nail |
| 5" Aspen           | N 35° E | 20.56 ft.          |
| 6' metal sign post | S 44° W | 2.4 ft. to face    |
- (All measurement taken to nail in side of tree)



Signed by John P. Goss  
 Surveyor's Michigan License No. 23509  
 U.S.F.S. No. E-15

Date April 10, 2000