

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

GOGEBIC

(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R44W

H-5

T___ R___

T___ R___

T___ R___

T___ R___

2. Property Controlling
in Section

S___

T___ R___

S___

T___ R___

3. Miscellaneous
Property in Sec.

S___

T___ R___

S___

T___ R___

**SURVEY &
REMONUMENTATION**

JAN 05 2001

SECTION

Received for record the
26TH day of MAY

A. D. 19 at 11:00 o'clock

A m., and recorded in
Liber 7 of CORNERS

on page 308

Cheerl Renne
Dep. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter Corner, Sections 10 & 15, T46N, R44W

I, John P. Goss, in a field survey on April 14, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 21, 1851.

Original bearing trees: Yellow Birch 20" S 38° W 17 links (11.22 ft.)
Yellow Birch 16" N 38° E 32 links (21.12 ft.)

Richard L. Drahn, 21564, on April 13, 1982, re-established the corner position on line between and equal distance from the Southeast and Southwest corners of Section 10, T46N, R44W. He set a 2" I.D. aluminum monument with a 3/4" aluminum cap, stamped to indicated the corner position. He established the following reference objects: 12" Y. Birch - N 16° W - 24.60 ft.; 8" Black Ash - N 41° E 27.64 ft.; 4" Sugar Maple - S 50° W - 17.47 ft.; 6' metal sign post - N 35° W 2.1 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On March 15, 1983, he recorded said corner in Liber 2, page 386 of Land Corners.

Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

FREE GROUP APPROVED

Richard L. Drahn 05/24/00
COUNTY B22465414740

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument, stamped to read: T.46 N., R.44 W.: 1/4; S-10, S-15; 1982; R.L.S. 21564: From which I established the following existing and new reference objects:

14" Yellow Birch	N 16° W	24.53 ft.	new nail
11" Black Ash	N 41° E	27.58 ft.	new nail
7" Sugar Maple	S 50° W	17.47 ft.	
7" Yellow Birch	S 80° E	29.00 ft.	
6' metal sign post	N 35° W	2.1 ft.	to face

(All measurement taken to nail in side of tree)

Signed by John P. Goss

Date April 14, 2000

Surveyor's Michigan License No. 23509

U.S.F.S. No. J-15

