

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gegebic County } ss.

For corners in

GOGBIC  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 46 N 44 W H-7  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_ **SURVEY &**  
T \_\_\_ R \_\_\_ **MONUMENTATION**

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_ JAN 05 2001

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_ SECTION

Received for record the  
26<sup>TH</sup> day of MAY  
A. D. 19 00 at 11:00 o'clock  
A m., and recorded in  
Liber 7 of CORNEES

page 309  
Cheyl Ruspe  
Dep. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Quarter Corner, Sections 15 & 22, T46N, R44W

I, John P. GOSS, in a field survey on April 19<sup>th</sup> 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7								●					
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on July 18, 1851.

Original bearing trees: Spruce 14" S 34° E 17 links (11.22 ft.)  
Cedar 16" N 22° W 13 links ( 8.58 ft.)

Richard L. Drahn, 21564, on October 19, 1981, restored corner position at recored bearing and distance from the remains of the two original bearing trees. Also he tied it in to some natural features and cedar stump called for in original notes; He set a 2" I.D. aluminum monument with a 3/4" aluminum cap, stamped to indicated the corner position; He established the following reference objects: 10" Red Maple - N 30° W - 13.60 ft.; 8" Black Ash - S 65° E - 41.61 ft.;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

8" Red Maple - S 08° W - 17.86 ft.; 6' metal sign post - North - 1.7 ft.

On March 10, 1982, he recorded said corner in Liber 2, page 232, of Land Corner.

No original evidences found.

Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

PEER GROUP APPROVED  
Richard L. Drahn 05/24/00  
COURT BARRISTER & SURETY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument stamped to read: T.46 N., R.44 W.; 1/4; S-15, S-22; 1981, R.L.S. 21564: from which I established the following existing and new reference objects:

12" Red Maple N 30° W 13.56 ft.  
9" Black Ash S 65° E 41.61 ft.  
10" Red Maple S 08° W 17.84 ft.  
7" Balsam N 47° E 13.83 ft.  
6' metal sign post North 1.7 ft. to face  
(All measurement taken to nail in side of tree)



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date April 19, 2000

U.S.F.S. No. N-15