

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County }

Received for record on
26th day of MAY
A. D. 2000 at 11:00 o'clock
A m, and recorded in
Liber 7 of CORNERS
310
Chester Ruppe
Dep. Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located in:

Corner Code #

1. Public Land Survey

T46N R44W

H-9

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___

T ___ R ___

S ___

T ___ R ___

3. Miscellaneous Property in Sec.

S ___

T ___ R ___

SURVEY & MONUMENTATION

JAN 05 2001

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter Section, Sections 22 & 27, T46N, R44W

I, John P. GOSS, in a field survey on April 12th 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1851.

Original bearing trees: Cedar 12" N 15° W 10 links (6.60 ft.)
Cedar 12" S 05° E 9 links (5.94 ft.)

Donald D. Lappala, 12585, on October 20, 1967, restored corner position from the decayed remains of the original bearing trees. The first a 24" cedar windwall and the second a large stump hole. He set a 2" I.D. iron pipe with a 3" bronze cap, stamped to indicated the corner position. He established the from bearing trees: 8" Hemlock - N 35° E - 54.4 ft.; 3" Red Maple - S 45° E - 24.4 ft.; 4" Sugar Maple - S 07° E - 57.5 ft. windwall.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On June 6, 1968, he recorded said corner in U.S.F.S. Liber, index No. R-15.

Found the first original bearing tree: now a 24" cedar windfall.

Found D. Lappala monument and accessories.

Act 74 research on file.

DEED GROUP APPROVED
Richard L. Drahn 05/24/00
COUNTY BARABOSKA, IOWA

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument stamped to read: T.46 N., R.44 W.; 1/4; S-22, S-27; R.L.S. 12585, 1967, from which I established the following existing and new reference objects:

12" Hemlock	N 35° E	54.22 ft.
5" Red Maple	S 45° E	24.30 ft.
10" Hemlock	S 20° W	11.77 ft.
4"by4" wood sign post	S 70° E	2.8 ft. to face
6' rail & sign	Due West	1.76 ft. to face

(All measurement taken to nail in side of tree)

Signed by John P. Goss

Surveyor's Michigan License No. 23509

U.S.F.S. No. R-15

Date April 12, 2000

