

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R 44W

I-2

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

**SURVEY &**

**REMONUMENTATION**

2. Property Controlling  
in Section

S \_\_\_ T \_\_\_

R \_\_\_

S \_\_\_ T \_\_\_

R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_

R \_\_\_

S \_\_\_ T \_\_\_

R \_\_\_

**JAN 05 2001**

**SECTION**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Quarter Corner, Sections 2 & 3, T46N, R44W

I, John P. Goss, in a field survey on March 22, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3	●	2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 19, 1851.

Original bearing trees: Y. Birch 16" S70°W 28 links (18.48 ft.)  
W. Pine 24" N50°E 18 links (11.88 ft.)

Richard L. Drahn, 21564, on May 5, 1982 restored corner position at record bearing and distance from the remains of the two original bearing trees. He set a 2" I.D. iron pipe with 3" cap, stamped to indicated the corner position. He established the following reference objects: 8" Red Pine (forked) - N 42°W 73.21 ft.; 5" red Pine - N 13° E - 49.41 ft.; 11" White Spruce - N 55° E - 71.70 ft.; 6' metal sign post - N 55° E - 2.7 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the white pine stump now burned and decayed of original bear tree.

Drahn recorded said corner on March 15, 1983 in Liber 2, Page 420 of Land Corners.

Found Drahn, monument and accessories.

Act 74 research on file.

PEER GROUP APPROVED

Richard L. Drahn 05/24/00  
COURT REGISTRAR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From found monument, stamped to read: T46N, R44W; 1/4; S-2, S-3; 1982; R.L.S. 21564: I established the following new and existing reference objects:

11" Red Pine (forked) N 42° W 73.30 ft. new nail  
12" Red Pine N 13° E 49.84 ft. new nail  
16" White Spruce N 55° E 71.81 ft. new nail  
6" Aspen S 32° W 11.57 ft.  
6' metal sign post N 55° E 2.7 ft. to face

(All measurement taken to nail in side of tree)

Signed by John P. Goss

Date March 22, 2000

Surveyor's Michigan License No. 23509

USFS. C-17

