

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

T46^WR 44^N

I-3

T R SURVEY &
T R REMONUMENTATION

2. Property Controlling in Section

S T R

JAN 05 2001

3. Miscellaneous Property in Sec.

S T R
S T R

SECTION

Received for record the
26TH day of MAY
A. D. 19 at 11:00 o'clock
A m., and recorded in
Liber 7 of CORNERS

on page 312
Cheryl Ruppe
Dep. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner, Sections 2, 3, 10 & 11, T46N, R44W

I, John P. Goss, in a field survey on March 2ND 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3								●				
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 19, 1851.

Original bearing trees: Spruce 16" S 51° E 61 links (40.26 ft.)
Y. Birch 14" N 74° W 46 links (30.36 ft.)

Richard L. Drahn, 21564, on April 19, 1982, re-established corner position by double proportionate method. He set a 2" I.D. aluminum pipe with 3/4" aluminum cap, stamped to indicated the corner position. He established the following reference objects: 10" Aspen - N39°E - 37.09' (slope dis.); 10" Aspen - N78°E 10.23'; 8" Aspen - S81°W - 57.35' (slope dis.); 6' metal sign post - S05°E 1.15'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 388 of Land Corners, on 3-15-83.

Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

FREE GROUP APPROVED
Richard L. Drahn 05/24/00
COURT RECONCILIATING

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument I established the following new and existing reference objects:

16" Aspen N 39° E 37.27 ft. (slope distance)
12" Aspen N 78° E 10.23 ft.
10" Aspen S 81° W 57.35 ft. (slope distance)
8" Balsam N 08° W 20.65 ft.
6' Metal sign post S 05° E 1.15 ft. (to face)

(All measurement taken to nail in side of tree)



Signed by John P. Goss

Date March 2, 2000

Surveyor's Michigan License No. 23509

USFS #E-17