

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } SA

For corners in

Gogebic  
(County)

Located In: Corner Code #

1. Public Land Survey

T46NR 44W I-4

T R  
T R SURVEY &  
T R MONUMENTATION

2. Property Controlling in Section

S T R  
S T R

3. Miscellaneous Property in Sec.

S T R  
S T R

JAN 05 2001

SECTION

Received for record lbs  
2673 day of MAY  
A. D. 2000 at 11:00 o'clock  
A m., and recorded in  
Liber 7 of CORNERS  
Page 313  
Cheerl Ruppel  
Dept Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner, Sections 10 & 11, T46N, R44W

I, John P. Goss, in a field survey on April 10<sup>th</sup> 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10	●	11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 19, 1851.  
Original bearing trees: Sugar 8" S 58° W 43 links (28.38 ft.)  
Sugar 14" N 34° E 13 links (8.58 ft.)

Richard L. Drahn, 21564, on April 12, 1982, re-established corner position on line between, and equal distance from the Southwest and the Northwest Section corners. He set a 2" I.D. aluminum monument with a 3/4" aluminum cap, stamped to indicated the corner position. He established the following reference objects:  
18" Red Pine - N 50° W - 35.97 ft.; 5" Balsam (Now down) N 48° E - 38.18 ft.;  
12" Red Pine - S 30° E - 65.61 ft.; 6' metal sign post - S 32° E - 2.4 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.  
On March 15, 1983, he recorded said corner in Liber 2, page 390 of Land Corners

Found R. Drahn, monument and accessories.

Act 74 research on file.

FILE GROUP APPROVED  
Richard L. Drahn 05/24/00  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument stamped to read: T.46 N., R.44 W.: 1/4; S-10, S-11; 1982; R.L.S. 21564: from which I established the following existing and new reference objects:

26" Red Pine N 50° W 36.34 ft. new nail  
15" Red Pine S 30° E 65.48 ft. new nail  
6" Spruce S 83° E 28.94 ft.  
6' metal sign post S 32° E 2.4 ft. to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date April 10, 2000

U.S.F.S. No. G-17