

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }
Saginaw County } ss.

Received for record this
26th day of MAY
A. D. 2000 at 11:00 o'clock
4 m., and recorded in
Liber 7 of CORNERS
on page 314
Chester Ruppe
Deputy Register of Deeds

Register of Deeds Stamp & File Number

For corners in
GOGEBIC
(County)

Located In: Corner Code #

1. Public Land Survey T46NR 44W I-5
T R SURVEY &
T R MONUMENTATION
T R
2. Property Controlling S T R
in Section S T R JAN 05 2001
3. Miscellaneous S T R
Property in Sec. S T R
SECTION

4. Lot No. , Recorded Plat
5. Private Claims
Section Corner, Sections 10, 11, 14 & 15, T46N, R44W

I, John P. Goss, in a field survey on April 10th 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1851.
Original bearing trees: Aspen 14" S 30° W 45 links (29.70 ft.)
Spruce 12" N 64° E 26 links (17.16 ft.)

Donald D. Lappala, 12585, on June 4, 1970, found corner position marked by intersection of fence lines east, west and South also found stump hole of spruce B.T. also North to natural features and line trees. He set a 2" I.D. iron pipe with 3" bronze tablet stamped to indicated the corner position. He established the following reference trees: 3" R. Maple - N 35° W - 28.9 ft.; 4" S. Maple N 10° E - 49.7 ft.; 4" S. Maple - N 50° E - 24.1 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On August 10, 1972, he recorded said corner in U.S.F.S. Liber, index J-17.

Found D. Lappala monument and accessories.


Act 74 research on file.

NEER GROUP APPROVED
Richard D. Dean 05/24/00
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the found monument, stamped T.46 N., R.44 W.; S-10, S-11, S-14, S-15; R.L.S. 12585; 1970; from which I established the following existing and new reference objects:

6" Red Maple	N 35° W	29.08 ft.
9" Sugar Maple	N 10° E	49.70 ft.
9" Sugar Maple	N 50° E	24.23 ft.
4" by 4" wood post & sign	Due N.	2.24 ft. to face
6' Rail & sign	S 55° E	1.58 ft. to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509
U.S.F.S. No. J-17

Date April 11, 2000