

# SURVEY & REMONUMENTATION

OCT 03 1996

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

### COMMISSION

For corners in

Gogebic  
(County)

Located in:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>46N</u> R <u>44W</u> | <u>I-6</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

Received for record the  
16<sup>th</sup> day of AUGUST  
A. D. 1996 at 10:30 o'clock  
A m., and recorded in  
Liber 5 of CORNERS

Page 401  
Ramona Collins, Deputy  
Register of Deeds  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 corner comm. to sec's. 14 & 15

I, John P. Goss, in a field survey on June 25, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 20th Aug., 1851. Set post.  
Original bearing trees: Cedar 14" S 85° E 41 links  
Hemlock 10" N 42° W 38 links

In June of 1970 Donald Lappala R.L.S. of U.S.F.S. set this corner by single proportionate measurement. It had a very old fence line West from corner and a old fence line East from corner. He recorded this corner in Liber 1 on pages 87 and 88. He established the following bearing trees and reference objects: Spruce- N 65° E- 39.0'; 9" Tamarack- S 38° E- 40.0'; 20" Spruce- S 27° W- 47.3'. This Liber is Liber 1 of Land Corners for Gogebic County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D. Lappala set a 2" iron pipe with 3" bronze cap stamped to note corner information.

I found the 2" iron pipe with 3" bronze cap as noted in D. Lappala certification and it checked with his witnesses. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2" iron pipe with 3" bronze cap I established the following bearing trees and reference objects.

10" Spruce	N 65° E	39.01'
12" Tamarack	S 38° E	40.02'
23" Spruce	S 27° W	47.29'
13" Ash	N 50° W	13.82'
6' rail & sign	N 04° E	1.5'



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date June 25, 1996