

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in
Gogebic Located In: Corner Code #
(County)

1. Public Land Survey T46NR 44W I-11
T___ R___
T___ R___ **SURVEY &**
T___ R___ **MONUMENTATION**
2. Property Controlling S___ T___ R___
in Section S___ T___ R___
3. Miscellaneous S___ T___ R___
Property in Sec. S___ T___ R___

Received for record the
26TH day of MAY
A. D. 1900 at 11:00 o'clock
A m., and recorded in
Liber 7 of CORNERS
page 317
Cheryl Rippe
Deputy Register of Deeds

Register of Deeds Stamp & File Number

SECTION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner, Section's 26, 27, 34 & 35, T46N, R44W

I, John P. Goss, in a field survey on March 30, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1851.
Original bearing trees: Sugar Maple 14" S 17° E 11 links (7.26 ft.)
Cedar 16" N 05° W 17 links (11.22 ft.)
Donald D. Lappala, 12585, on Oct. 16, 1967, restored corner position from the decayed and fire charred stumps of both of the original bearing trees. He set a 2" I.D. Iron pipe with 3" bronze tablet stamped, to indicated the corner position. He established the following reference objects: 5" S. Maple - West 13.0 ft.; 7" S. Maple - N 12° E - 45.5 ft.; 5" S. Maple (DEAD) - S 05° E - 25.5 ft. IN 1989 D.D., P.S. & J.D. added a 9" S. Maple - S 35° E - 28.08 ft.;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

4"x4" wood Post - S 20° E - 2.5 ft.
He recorded said corner on June 6, 1968, in Liber V-17 of U.S.F.S. Book

Found Lappala Monument and all accessories from above.

Act 74 research on file.

BEEN GROUP APPROVED
Richard B. Decker 05/24/00
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From found monument stamped to read: T.46 N., R.44 W.; S-26, S-27, S-34, S-35;
R.L.S. 12585, 1967; I established the following existing and new reference objects:

8" Sugar Maple	N 82° W	12.78 ft.
15" Sugar Maple	N 12° E	45.54 ft.
11" Sugar Maple	S 35° E	28.05 ft. new nail
4"x4" Wood post	S 20° E	2.5 ft. to face
6' metal rail & sign	N 16° W	1.24 ft. to face

(All measurement taken to nail in side of tree)

Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date March 30, 2000

USFS. No. V-17

