

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in

GOGEBIC

(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R44W

T. 9

T___ R___

MONUMENTATION

T___ R___

T___ R___

2. Property Controlling in Section

S___

T___ R___

JAN 05 2001

S___

T___ R___

3. Miscellaneous Property in Sec.

S___

T___ R___

SECTION

S___

T___ R___

Received for record the
26TH day of MAY

A. D. 1900 at 11:00 o'clock

A m., and recorded in

Liber 7 of CORNERS

on page 320

Cheryl Ruspe
 Deputy Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter corner, Sections 23 & 26, T46N, R44W

I, John P. Goss, in a field survey on May 2, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Corner established by Austin Burt, in 1851. Corner 8" Sugar Maple.
 Original bearing tree: Sugar Maple 12" - N 65° W - 7 links (4.62ft.).
 Donald D. Lappala, 12585, on October 17, 1967, restored corner position from the stump of 1/4 corner tree and decayed stump of original bearing tree. Further verified by retracement measurement to pond to the East. He set a 2" I.D. iron pipe with 3" bronze tablet, stamped to indicate the corner position. He established the following reference objects: 5" Elm (dead) - N 78° W - 18.1 ft. 12" Sugar Maple - N 42° E - 23.9 ft.; 6" Yellow Birch - S 07° W - 4.5 ft. On June 6, 1968, he recorded said corner in U.S.F.S. Liber, Index No. R-19.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No original evidence found.

Found Donald D. Lappala, monument and accessories.


Act 74 research on file.

NEED GROUP APPROVED
Richard R. ... 05/24/00
 COUNTY REGISTRATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 From found monument, stamped to read: T.46 N., R.44 W.; 1/4; S-23, S-26; R.L.S. 12585; 1967; from which I established the following existing and new reference objects:

15" Sugar Maple	N 42° E	24.23 ft.
11" Yellow Birch	S 07° W	4.47 ft.
7" Sugar Maple	S 47° W	13.96 ft.
4"x4" wood sign post	N 73° W	2.98 ft. to face
6' rail & sign	S 67° E	1.74 ft. to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss
 Surveyor's Michigan License No. 23509

Date May 3, 2000

U.S.F.S. No. R-19