

Register's Office }
 Gogebic County } 321

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Received for record the
21st day of MAY
 A. D. 2000 at 11:00 o'clock
A m., and recorded in
 Liber 7 of CORNERS

For corners in

Gogebic
 (County)

Located in:

Corner Code #

1. Public Land Survey

T46NR 44W

J-11

T___ R___

SURVEY &

T___ R___

MONUMENTATION

T___ R___

2. Property Controlling
 in Section

S___

T___ R___

S___

T___ R___

JAN 05 2001

3. Miscellaneous
 Property in Sec.

S___

T___ R___

S___

T___ R___

SECTION

321

Cheryl Rippe
 Deputy Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter Corner Sections 26 & 35, T46N, R44W

I, John P. Goss, in a field survey on March 30th 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	19		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1851.

Original bearing trees: Tamarack 10" N 54° E 29 links (19.14 ft.)
 Tamarack 8" S 17° W 5 links (3.30 ft.)

Donald D. Lappala, 12585, on Oct. 16, 1967, restored corner position at record bearing and distance from the decayed stumps of the two original bearing trees. He set a 2" I.D. iron pipe with 3" bronze tablet stamped, to indicated the corner position. He established the following reference objects: 4" Tamarack N 50° W - 7.1 ft.; 4" Tamarack - N 53° E - 26.4 ft.; 4" Tamarack - S 84° E 43.8 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in U.S.F.S. Liber on Page V-19, on June 6, 1968.

Found Lappala monument and accessories.

Act 74 research on file.

BEAR GROUP APPROVED
Richard D. Deahn 05/24/00
 COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument stamped to read: T.46 N., R.44 W.; 1/4; S-26, S-35; R.L.S. 12585; 1967, from which I established the following existing and new reference objects:

5" Tamarack N 50° W 7.10 ft.
 7" Tamarack N 53° E 26.40 ft.
 6" Tamarack S 84° E 43.86 ft.
 4"x4" Wood post & sign S 84° W 2.95 ft. to face
 6' metal rail & sign N 70° E 1.52 ft. to face

(All measurement taken to nail in side of tree)

Signed by John P. Goss
 Surveyor's Michigan License No. 23509

Date March 30, 2000

USFS. No. V-19

