

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

1. Public Land Survey

T46NR 44W K-3

T R

T R

2. Property Controlling
in Section

S T R SURVEY &
S T R REMONUMENTATION

3. Miscellaneous
Property in Sec.

S T R
S T R JAN 05 2001

Received for record the
26TH day of MAY
A. D. 2000 at 11:00 o'clock
 m., and recorded in
Liber of CORNERS
on page 323
Robert Rippe
Dep. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat SECTION

5. Private Claims

Section Corner, Sections 1, 2, 11 & 12, T.46 N., R.44 W.

I, John P. Goss, in a field survey on March 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 20, 1851.

Original bearing trees: Cedar 14" S 59° W 27 links (17.82')
Cedar 8" N 68° E 20 links (13.20')

Richard L. Drahn, 21564, restored corner position at record bearing and distance from the remains of the two original bearing trees on Sept. 17, 1981. He set a 2" I.D. aluminum pipe with 3/4" cap, stamped to indicated the corner position. He established the following reference objects: 10" Cedar - N 12° W - 70.64 ft.; 8" Black Spruce - N 51° E - 47.72 ft.; 7" Black Spruce - S 19° E - 27.24 ft. no down; a 6' metal sign post - S 20° E - 1.8 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 236 of Land Corners on 3-10-82.

Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

NOTE: Drahn monument is a 3/4 inch aluminum marsh rod.

DEER GROUP APPROVED

Richard L. Drahn 05/24/00
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From found monument and cap stamped to read: T.46 N., R.44 W.; S-1, S-2, S-11, S-12; 1981 R.L.S. 21564, I established the following new and existing reference objects:

14" Cedar N 12° W 70.27 ft. new nail
11" Black Spruce N 51° E 47.70 ft. new nail
8" Spruce S 80° W 19.90 ft.
6' metal sign post S 20° E 1.8 ft. to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date March 8, 2000

USFS # E-21