

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R44W

K-5

T\_\_\_ R\_\_\_

T\_\_\_ R\_\_\_

T\_\_\_ R\_\_\_

**SURVEY &  
 MONUMENTATION**

2. Property Controlling  
 in Section

S\_\_\_

T\_\_\_ R\_\_\_

S\_\_\_

T\_\_\_ R\_\_\_

3. Miscellaneous  
 Property in Sec.

S\_\_\_

T\_\_\_ R\_\_\_

S\_\_\_

T\_\_\_ R\_\_\_

JAN 05 2001

Received for record the  
26<sup>th</sup> day of MAY

A. D. 19 20 at 11:10 o'clock

A m., and recorded in

Liber 7 of CORNERS

on page 325

Cheryl Rupp

Dep. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Section Corner, Sections 11, 12, 13 & 14, T46N, R44W

I, John P. Goss, in a field survey on March 22, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 20, 1851.

Original Bearing trees: Sugar 12" S 55° W 33 links (21.78 ft.)  
 Hemlock 8" N 34° E 21 links (13.86 ft.)

Richard L. Drahn, 21564, on October 26, 1982, re-established corner position by double proportionate methods. He set a 2" aluminum monument with 3/4" cap, stamped to indicated the corner position. He established the following references objects: 8" R. Maple - N 55° W - 24.05 ft.; 17" W. Spruce - N 24° W - 25.08 ft.; 6" R. Maple - S 09° W - 9.36 ft.; 6' metal sign post - S 05° E - 2.0 ft. He recorded said corner on March 15, 1983, in Liber 2, Page 400 of

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Land Corners.

Found Drahn's monument and accessories.

Act 74 research on file.

NEER GROUP APPROVED

Richard L. Drahn 05/24/00

COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument stamped to read: T46N-R44W; S-11, S-12, S-13, S-14; 1982; R.L.S. 21564: I established the following New and existing reference objects:

9" Red Maple N 55° W 24.10 ft. new nail  
 18" White Spruce N 24° W 25.08 ft.  
 9" Red Maple S 09° W 9.36 ft.  
 5" Balsam S 44° E 12.64 ft.  
 6' metal sign post S 05° E 2.0 ft. to face  
 (All measurement taken to nail in side of tree)



Signed by John P. Goss

Date March 22, 2000

Surveyor's Michigan License No. 23509

USFS. J-21