

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in  
GOGEBIC  
(County)

Located In: Corner Code #

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

T46NR R44W K-10  
T\_\_R\_\_  
T\_\_R\_\_ **SURVEY &**  
T\_\_R\_\_ **MONUMENTATION**  
S\_\_T\_\_R\_\_  
S\_\_T\_\_R\_\_ **JAN 05 2001**  
S\_\_T\_\_R\_\_

SECTION

Received for record the  
26<sup>th</sup> day of MAY  
A. D. 2000 at 11:10 o'clock  
A m., and recorded in  
Liber 7 of CORNERS  
page 328  
*Chester Rippe*  
Reg. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
Quarter Section, Sections 25 & 26, T46N, R44W

I, John P. Goss, in a field survey on May 3, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
Corner established by Austin Burt, in 1851.  
Original bearing trees: Yellow Birch 10" N 03° E 9 links ( 5.94 ft.)  
Hemlock 24" S 85° W 18 links (11.88 ft.)  
Donald D. Lappala, 12585, on October 19, 1967, restored corner position at record bearing and distance from the decayed stumps of the two original bearing trees. Verified further by measurement along section line north and south from corner to recoverable record natural features. He set a 2" I.D. iron pipe with a 3" bronze tablet, stamped to indicated the corner position. He established reference objects: 4" Spruce - N85°W-17.1 ft.; 4" Spruce(Dead) - N07°W-11.0 ft.;
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
4" Cedar - S50°W - 37.0 ft.; in 1989 U.S.F.S. added 8" Spruce - N38°E-24.64 ft.  
4"x4" wood sign post - N02°W-2.43 ft.  
On June 6, 1968, he recorded said corner in U.S.F.S. Liber in Index T-21.

No original evidence found.

Found Donald D. Lappala, monument and accessories.


Act 74 research on file.

PEER GROUP APPROVED  
*Richard P. Dean* 05/24/00  
COUNTY REGISTER OF DEEDS

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
From found monument, stamped to read T.46 N., R.44 W.; 1/4; S-25, S-25; R.L.S. 12585; 1967; from which I established the following existing and new reference objects:

10" Spruce	N 85° W	17.05 ft.
11" Cedar	S 50° W	37.16 ft.
10" Spruce	N 38° E	24.23 ft. new nail
4" by 4" wood sign post	N 02° W	2.29 ft. to face
12" Cedar	S 63° E	52.25 ft.

(All measurement taken to nail in side of tree)



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date May 4, 2000

U.S.F.S. No. T-21