

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in

GOGEBIC

(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R 44W

L-3

T\_\_\_ R\_\_\_

SURVEY &

T\_\_\_ R\_\_\_

MONUMENTATION

T\_\_\_ R\_\_\_

2. Property Controlling in Section

S\_\_\_ T\_\_\_ R\_\_\_

JAN 05 2001

3. Miscellaneous Property in Sec.

S\_\_\_ T\_\_\_ R\_\_\_

SECTION

Received for record on  
26<sup>th</sup> day of MAY

A. D. 2000 at 11:10 o'clock

A m., and recorded in

Liber 7 of CORNER

on page 329

Cheryl Repp  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Quarter corner, Sections 1 & 12, T46N, R44W

I, John P. Goss, in a field survey on May 5, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 20, 1851.

Original bearing trees: Y. Birch 14" S 12° W 63 links (41.58 ft.)

Y. Birch 8" N 19° E 21 links (13.85 ft.)

Richard L. Drahn, 21564, on June 3, 1975, restored corner position at record bearing and distance from the decayed remains of the two original bearing trees. Further verified by measurements to natural features calls. He set a 2½" I.D. iron pipe with 3" bronze tablet, stamped to indicated the corner position. He established the following reference objects: 5" Black Ash - N 75° W - 39.9 ft.; 4" Red Elm - N 89° E - 17.2 ft.; 12" Cedar - S 29° W - 59.3 ft.; 7' metal sign

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: post - S 48° E - 1.4 ft. He recorded said corner on Jan. 27, 1976, in Liber 1, page 156 of Land Corners.

No original evidence found.

Found Richard L. Drahn, Monument and accessories.

Act 74 research on file.

DEED GROUP APPROVED  
Richard L. Drahn 05/24/00  
 COUNTY Gogebic

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument, stamped to read: T.46 N., R.44 W., 1/4; S-1, S-12; R.L.S. 21564; 1975; from which I established the following existing and new reference objects:

7" Black Ash	N 75° W	40.08 ft.
8" Red Elm	N 89° E	17.36 ft.
15" Cedar	S 29° W	59.02 ft.
5" Ash	N 31° E	10.28 ft.
7' metal sign post	S 48° E	1.4 ft. to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss

Date May 5, 2000

Surveyor's Michigan License No. 23509

U.S.F.S. No. E-23