

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

1. Public Land Survey

T46^WR 44^N L-5

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

**SURVEY &
REMONUMENTATION**

JAN 05 2001

SECTION

Received for record the
26TH day of MAY
A. D. 2000 at 11:10 o'clock
A m., and recorded in
Liber 7 of CORNERS

page 330
Cheerl Ruppe
Dep. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 corner common to 12 & 13, T46N, R44W

I, John P. Goss, in a field survey on Feb. 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 21, 1851.

Original bearing trees: Yellow Birch 16" S 35° E 33 links (21.78')
Yellow Birch 10" N 51° W 31 links (20.46')

Richard L. Drahn, 21564, on October 27, 1982, re-established corner position by single proportionate method between the Southeast and Southwest Section corners. He set a 2" Aluminum monument with 3/4" Aluminum cap, stamped to indicated the corner position. He established the following reference objects: 4" Aspen - S 60° E - 9.81 ft.; 10" Balsam - S 21° E - 52.07 ft.; 9" Aspen - N 85° W - 51.13 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 402 of Land Corners, on 3-15-83.

Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

HEREBY APPROVED
Richard L. Drahn 05/24/00
COLLECTOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument I established the following new and existing reference objects:

8" Aspen	S 60° E	9.91 ft.	new nail
12" Balsam	S 21° E	52.17 ft.	
13" Aspen	N 85° W	51.02 ft.	new nail
6" Steel rail & sign	N 05° E	2.37 ft.	to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date March 1, 2000

USFS # J-23