

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } sr.

Received for record the
14TH day of MAY
 A. D. 1998 at 3:10 o'clock
P m., and recorded in
 Liber 6 of CORNERS

on page 351
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 44W M-2
T R
T R
T 46N R 43W A-2

2. Property Controlling
 in Section
 3. Miscellaneous
 Property in Sec.

S T R
 S T R
 S T R
 S T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner 1 & 6; T.46 N., R.43-44 W.

Richard L. Drahn in a field survey on April 9, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/9/1847. Original B.T.s: --- Sugar 8" S.72 E. 12 links (7.92') --- Cedar 14" N.24 W. 35 links (23.10') ---
 Corner restored by Richard L. Drahn (21564) on 5/27/82 from the remains of the two original B.T.s. He set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing trees:

5"	Twin White Spruce	N.73 W.	7.14'
5"	Tamarack	N.33 E.	43.48'
12"	White Spruce	S.51 E.	34.99'
6'	Steel sign rail	N.07 E.	2.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County; Liber 2, Page 406.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

8"	Twin White Spruce	N.71 W.	7.14'
9"	Tamarack	N.34 E.	43.52'
15"	White Spruce	S.50 E.	34.68' (new nail)
6'	Steel sign rail	N.06 E.	2.18'

Only a stump hole remains of the original Sugar bearing tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

5" Black Cherry N.77 E. 40.64'

PEER GROUP APPROVED

Richard L. Drahn 5/13/98
 COUNTY REGISTER



Signed by Richard L. Drahn Date April 12, 1998

Surveyor's Michigan License No. 21564