

**SURVEY & REMONUMENTATION**

SEP 08 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Gogebic  
(County)

Located In: Corner Code #

1. Public Land Survey

T 46N R 44W M-4  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T 46N R 43W A-4

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 12 & 7; T.46 N., R.43-44 W.

I, Richard L. Drahn in a field survey on April 9, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/9/1847. Original B.T.s --- Y. Birch 18" S.70 E. 30 links (19.80') --- Y. Birch 12" N.53 W. 13 links (8.58') ---

Corner position re-established by Richard L. Drahn (21564) on 11/1/82 by single proportionate methods. He set a 2" X 30" aluminum pipe with a 3 $\frac{1}{4}$ " stamped aluminum cap and the following new B.T.s:

8"	Twin White Ash	N.55 E.	42.09'
4"	Sugar Maple	S.29 E.	28.79'
5"	Sugar Maple	S.54 W.	12.89'
6'	Steel sign rail	S.01 E.	1.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County, Liber 2, Page 410 on 3/15/83.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

11"	Twin White Ash	N.52 E.	41.84'	(new nail)
7"	Sugar Maple	S.30 E.	28.81'	
8"	Sugar Maple	S.54 W.	12.91'	
6'	Steel sign rail	South	1.75'	

No evidence remains of the original corner or bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

5" Red Maple S.03 W. 26.40'

PEEB GROUP APPROVED  
Richard L. Drahn 5/13/98  
 COUNTY REGISTRAR

Register's Office }  
 Gogebic County } ss.

Received for record the  
14<sup>TH</sup> day of MAY

A. D. 1998 at 3:10 o'clock

P m., and recorded in  
 Liber 6 of CORNERS

on page 353  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Richard L. Drahn

Date April 12, 1998

Surveyor's Michigan License No. 21564