

**SURVEY & REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- |                                    |                             |            |
|------------------------------------|-----------------------------|------------|
| 1. Public Land Survey              | T <u>46</u> N R <u>43</u> W | <u>A-8</u> |
|                                    | T _____ R _____             | _____      |
|                                    | T _____ R _____             | _____      |
|                                    | T <u>46</u> N R <u>44</u> W | <u>M-8</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____     | _____      |
|                                    | S _____ T _____ R _____     | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____     | _____      |
|                                    | S _____ T _____ R _____     | _____      |

Register's Office } ss.  
 Gogebic County }

Received for record the  
23<sup>RD</sup> day of JULY  
 A. D. 1998 at 11:35 o'clock  
A m., and recorded in  
 Liber 7 of CORNERS  
 on page 19  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 19 & 24; T.46 N., R.43-44 W.

I, Richard L. Drahn in a field survey on July 18, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/9/1847. Original B.T.s --- Y. Birch 20" S.37 E. 49 links (32.34') --- Sugar 12" N.49 W. 39 links (25.74') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner at record bearing and distance from the remains of the two original bearing trees. The first is a 24-34" Y. Birch stump, decayed to well below ground line. The second one is now a series of root holes with fragments of badly decayed Sugar Maple wood. Corner position lays within five feet of a mathematical split of the section line as determined with a sub-meter GPS receiver. No evidence found of subsequent corner restoration.

Corner research on file with Gogebic County records.

FREE GROUP APPROVAL  
Richard L. Drahn 7/22/98  
 COURT REGISTRAR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner I set a 2½" X 30" aluminum pipe with a 3½" aluminum pipe stamped to indicate the corner position and the following new B.T.s:

- |     |                 |         |        |
|-----|-----------------|---------|--------|
| 6"  | Red Maple       | N.30 W. | 16.79' |
| 10" | Sugar Maple     | S.55 E. | 24.24' |
| 5"  | Sugar Maple     | S.18 W. | 35.54' |
| 6'  | Steel sign rail | S.28 E. | 2.07'  |

Resource grade GPS: Lat. 46-22-09.15 N  
 Long. 89-44-25.26 W



Signed by Richard L. Drahn Date July 19, 1998

Surveyor's Michigan License No. 21564