

**SURVEY &
REMONUMENTATION**

AUG 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic _____
(County)

Located In:

Corner Code #

1. Public Land Survey

T46NR 43W A-9
T46NR 44W M-9

2. Property Controlling
in Section

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sec. cor. comm. to sec's. 19, 30, 24 & 25

I, John P. Goss, in a field survey on June 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on Aug. 8, 1847. Set Cedar post.
Original bearing trees: 1. Cedar 16" S 56° W 28 links
2. Hemlock 12" N 65½° E 9 links
3. Hemlock 12" S 33° E 67 links
4. Hemlock 6" N 34° W 30 links.

Richard Drahn, RLS, on May 14, 1975. Restored corner position at record bearing and distance from remains of the following original bearing trees.
1. Portion of large Cedar stump. 3. Large Hemlock windfall decayed to ground line. 4. Stump hole with Hemlock roots & bark. Also with line tree ties.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He set a 2" iron pipe with 3" cap stamped to indicated corner position, with the following references: 10" S. Maple- S72°E- 25.0'; 9" S. Maple- N66°E- 23.8'; 9" S. Maple- N05°E- 23.6'. Recorded in Liber 1, page 158 of Land Corners.

Found Richard Drahn, 2" Iron pipe with 3" bronze table. It checked with his witnesses. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED
Richard L. Drahn 7/15/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2" I.D. iron pipe with 3" circular bronze tablet which read: T.46 N., R.43-44 W.; S-24, S-25, S-19, S-30; R.L.S. 21564; 1975. I established the following existing and new bearing trees and reference objects.

11" Sugar Maple (stub)	S 72° E	25.01'	
12" Sugar Maple	N 66° E	23.80'	
12" Sugar Maple	N 05° E	23.63'	
6" Sugar Maple	S 75° W	6.60'	
7' Metal sign post	North	2.1' (to face of post)	
6' Rail & sign	South	1.7' (to face of rail)	

(measurement to nail in side of tree)

Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date June 14, 1997

Fed. No. R-25

Register of Deeds Stamp & File Number

Received for record the
16TH day of JULY
A. D. 1997 at 1:40 o'clock
P m., and recorded in
Liber 1 of CORNERS
on page 167
Collen M. Kuebel
Deputy Register of Deeds

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

