

SURVEY &
REMONUMENTATION

DEC 15 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

For corners in SECTION

Gogebic
(County)

Located In: Corner Code #

- | | | | |
|------------------------------------|---------|-----------------|------|
| 1. Public Land Survey | | T 46N R 45W | A-10 |
| | | F _____ R _____ | |
| | | T _____ R _____ | |
| | | T 46N R 46W | M-10 |
| 2. Property Controlling in Section | S _____ | T _____ R _____ | |
| | S _____ | T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ R _____ | |
| | S _____ | T _____ R _____ | |

Received for record the
25TH day of NOVEMBER

A. D. 1998 at 10:00 o'clock
A m., and recorded in
Liber 7 of CORNERS

on page 87
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner 30 & 25; T.46 N., R.45-46 W.

I, Richard L. Drahn in a field survey on November 3, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 9/1/1847. Original B.T.s --- Cedar 6" S.15 E. 20 links (13.20') --- 8" Cedar N.80 W. 8 links (8.28') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the remains of the two original B.T.s. The first is a badly decayed 8-12" Cedar with portions of both blaze faces and overgrowth still evident. the second one is now a very badly decayed 10-12" downed Cedar.

Corner research on file with Gogebic County records.

DEED GROUP APPROVED
Richard L. Drahn 11/24/98
COUNTY _____

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' aluminum rod with a 3/4" stamped aluminum cap and the following new B.T.s:

10"	Cedar	N.09 W.	33.28'
8"	Hemlock	S.37 E.	28.53'
9"	Cedar	N.70 E.	15.17'
6'	Steel sign rail	S.65 W.	2.44'



Signed by Richard L. Drahn Date November 9, 1998

Surveyor's Michigan License No. 21564

USFS T-1