

DEC 15 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in _____

Gogebic (County)	Located In:	Corner Code #
1. Public Land Survey	T 46 N R 45 W	B-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Received for record the
30th day of OCTOBER
A. D. 1998 at 9:05 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 66.
Ramona Collins Deputy
Register of Deeds
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/2 Corner 6 & 7; T.46 N., R.45 W.

Richard L. Drahn, in a field survey on October 9, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3	●											
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 7/21/1851. Original B.T.s --- 12" Hemlock S.55 E. 30 links (19.80') --- 14" Cedar N.67 W. 7 links (4.62') ---

C.E. Haight, on 7/29/35 recovered a 24" scribed Cedar B.T. at this location. He placed a location poster on a 8" Maple from which the B.T. lay NE 8 ft.

R. Drahn and M. Bale, on 7/7/95 recovered both B.T.s at this location and set a 4" squared Cedar post at the original corner location. Haight's 1935 tag tree was then a 13" Red Maple with the nails still attached.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position found marked by my 1995 Cedar post at record bearing and distance from the two original B.T.s. The first is a 12-14", almost completely decayed Hemlock stump. The second one is now a 24" live Cedar with all scribing and the measuring notch still visible. 1935 tag was located at the base of the original B.T.

Corner research on file with Gogebic County records.

PEER GROUP APPROVED
Richard L. Drahn 10/27/98
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' aluminum rod with a stamped 3 1/2" aluminum cap and the following new B.T.s:

9"	Cedar	N.28 W.	25.24'
9"	Cedar	S.72 E.	33.36'
18"	Hemlock	S.17 W.	27.15'
6'	Steel sign rail	S.37 E.	2.87'



Signed by Richard L. Drahn Date October 18, 1998

Surveyor's Michigan License No. 21564